BRUHAT BANGALORE MAHANAGARA PALIKE

BBMP/2020-21/OW/WORK_INDENT41628

APPROVED SCHEDULE - B

No.EE/BTP/BBMP/E-PMT/01/2020-21, Date: 05.05.2020

Name of Work:Desilting and footpath improvements in various roads of Sahakarnagara and surrounding areas inw ard no. 8, kodigehalli

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of BHARATH S ( )	
				In Figures	In Words
1	1658.88	Removing and refixing stone slabs of drains and pointing in CM 1:3 (Page No. 27, Item No. 5.33, PWDSR 2018-19)	Sqm	104.0	Rupees One Hundred Four Only
2	512	KSRRB 300-2 : Earth work excavation by manual means in Ordinary soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods complete as per specifications complete as per specifications MORTH chapter 3 (Page No. 143, Item No. 19.1, PWDSR 2018-19)	Cum	177.4	Rupees One Hundred Seventy Seven and Forty Paise Only
3	184.32	Providing and laying in position reinforced cement concrete M20 mix with stone aggregates 20mm and downsize for slab (including steel reinforcement) including centering and shuttering, maching mixed, concrete laid in layers not exceeding 15cm thick well compacted cost of all materials, labour, HOM of machineries, curing complete as per specifications. - 100 mm thick (Approved data rate enclosed)	Sqm	1963.5	Rupees One Thousand Nine Hundred Sixty Three and Fifty Paise Only
4	435	Lead for Disposal of Debris shall be payable at carriage rates by Mechanical means inlcuding loading and unloading. From 0.00 to 2.00 Km (Page No.123)	Cum	81.8	Rupees Eighty One and Eighty Paise Only

Signature of the Contractor

29/09

Executive Engineer
Byarayanapura Division
BBMP, Bangalore - 92

29/09